

VTA's BART Silicon Valley Phase II Extension Project

28th Street / Little Portugal
Community Working Group

May 13, 2020



Agenda

- Today's Format
- Follow-up Items
- CWG Member Report Back
- Phase I Update
- Phase II Update
- Next Steps


Quick GoToWebinar Guide

Mute/Unmute 

'Raise Hand' 

Meeting Handouts 

Ask a Question 



The screenshot shows the GoToWebinar interface with the following sections:

- Audio:** Includes a 'Sound Check' indicator and three icons: a microphone (muted), a document (handouts), and a hand (raise hand). Below these are radio buttons for 'Computer audio' (selected) and 'Phone call'. A 'MUTED' status is shown with a microphone icon. A dropdown menu shows 'Microphone (HD Webcam C510)'. A volume slider is present. Another dropdown menu shows 'Speakers (High Definition Aud...)'.
- Handouts: 2** (indicated by a dropdown arrow):
 - 2017-05-05_11-59-21.png
 - GTM iOS.jpeg
- Questions:** A text input field with the placeholder '[Enter a question for staff]' and a 'Send' button.
- Footer:** 'Multi sessions different registrants' and 'Webinar ID: 980-960-603'.



Today's Meeting Format

- Gretchen is facilitating
- Joe is managing the Go to Webinar app
- Microphones will be muted during each agenda item / presentation
- At the end of each agenda item there will be a question round. Joe will unmute members one-by-one during the question round.
 - You can also write in questions using the Questions box on the Go to Webinar app
- Please contact Gretchen after if you have any additional comments or questions.



Upcoming Meetings – 28th Street / Little Portugal

- **Upcoming 28th Street / Little Portugal CWG Dates**
 - July 2020 – Date TBD, 4:00 PM
 - September 15, 2020, 4:00 PM
 - November 17, 2020, 4:00 PM
- **VTA Board of Directors vta.org/about/board-and-committees**
 - June 4, 2020, 5:30 PM
- **Gretchen / Kate will email alerts for other meetings, e.g. Board Workshops**



Follow-Up Items

Gretchen Baisa, VTA



Follow-up Items – 28th Street / Little Portugal

- Send link to BART Phase II video – ✓
- Send link to playbook once finalized – *Noted*
- Send date for Santa Clara Council Meeting TOC Workshop Presentation – ✓
- Send the small business survey link to Small Business Task Force for beta testing – ✓
- Provide link to Airport RFQ responses in meeting summary – ✓



Questions



CWG Member Report Back



Report Back

- Carlos Diaz *Alum Rock Business Network*
- Connie Alvarez *Alum Rock Santa Clara Street Business Association*
- Elma Arredondo *Alum Rock Urban Village Advocates (ARUVA)*
- Terry Christensen *CommUniversity*
- Cobán López *Cristo Rey San José Jesuit High School*
- Chris Patterson-Simmons *East Santa Clara Street Business Association*
- Helen Masamori *Five Wounds / Brookwood Terrace Neighborhood Action Coalition*
- Davide Vieira *Five Wounds National Portuguese Parish*
- Bill Rankin *Friends of Five Wounds Trail*
- Danny Garza *Plata-Arroyo Neighborhood Association*
- Ricardo Agredano *Portuguese Organization for Social Services and Opportunities (POSSO)*
- Eric Thacker *Northside Neighborhood Association*
- Justin Triano *Ride East Side San José (Ride ESSJ)*
- Jeff Levine *Roosevelt Park Neighborhood Association*
- Kathy Ericksen *Somos Mayfair*



Phase I Update

Gretchen Baisa, VTA






Phase I Update

- Major Milestones:
 - BART started pre-revenue operations on April 20
 - Next Step: CPUC Certification
- BART Service During Shelter in Place Orders:
 - With service reduced during the shelter in place order, trains will run every 30 minutes on weekdays and every 24 minutes on weekends
- Revenue Service Date – To Be Announced




Framework to Passenger Service



- Significant progress made in System Safety Certification
- Systems Safety Certification Verification Report will be submitted 21 days prior to revenue service
- Green diamonds  represent completed milestones; red diamond  is the upcoming milestone



New BART Map



For real-time information, visit www.bart.gov


© BART 2010 10-11-2020

New BART Map

Before



After



Questions


Phase II Update

Bernice Alaniz, Ronak Naik, VTA



Single-Bore with Center Platform

- Concurrent to pursuing Federal funding, VTA and BART explored a larger single-bore tunnel with side-by-side tracks and center platform
- Engineering on the larger single bore with center platform was advanced to 10% design and showed higher projected costs and risks, thus prompting consideration of alternatives



Approximately 56-foot diameter
Tunnel Boring Machine

Criteria for Evaluation of Tunnel Configurations

1. Funding constraints
2. Federal funding process
3. Environmental clearance
4. Construction impacts
5. Contracting risk
6. Innovation opportunities
7. Consistency with BART system



BART's Operational Concerns for Stacked Configuration

Emergency Egress


Enclosed stairwells in the tunnel sections as a means for emergency evacuation is not considered intuitive for passengers

Operations

Challenges with train operations due to ramps/transitions and associated emergency egress

Ventilation

Proposed designs differ from typical BART underground system and would require specialized training of employees



Addressing BART's Operational Concerns

- Use 13th Street and Stockton Avenue mid-tunnel facilities to optimize ventilation, emergency evacuation, and provide operational flexibility
 - Limit transitions (ramps) between stacked and side-by-side track configurations to two locations (at ventilation facilities)
 - Provide emergency evacuation platforms at ventilation facilities
 - Provide crossovers (switches) for operational flexibility



Project Alignment

LEGEND

- Phase I Alignment
- Phase II Ground-Level Alignment
- Phase II Single-Bore Tunnel Alignment
- Ventilation Facility




Summary

- Two optimized concepts presented at the April 17 Board of Directors Special Meeting
- Concepts address BART's main operational concerns for single-bore stacked configuration
- Staff reviewed both concepts through the lens of public and Board feedback including minimizing street level impacts, business/community disruptions, and pre-established criteria (cost, schedule, risks, etc.)




Optimized Single-Bore Tunnel Concept

- Provides the most opportunity to minimize street-level impacts
- Provides opportunity for further optimization
- Addresses BART's operational concerns related to emergency egress, operations, and ventilation



Optimized Single-Bore Tunnel Concept



SANTA CLARA STATION

Newhall Maintenance Facility


**BERRYESSA/
NORTH SAN JOSÉ STATION**

**28TH STREET/
LITTLE PORTUGAL STATION**


**DOWNTOWN
SAN JOSÉ STATION**

DIRIDON STATION


**Side-by-Side
Single-Bore**



**Stacked
Single-Bore**




Ventilation Facility




Optimized Single-Bore Tunnel

- Single-bore tunnel with stacked track and platform configuration through downtown segment (13th Street to Stockton Avenue)





- Construction of emergency egress center platform adjacent to the ventilation facilities on either end of the Downtown/Diridon segment





- Cut-and-cover construction of 28th Street/Little Portugal Station and emergency egress platforms at 13th Street and at Stockton Avenue facilities

Track Configuration

- One single-bore tunnel for entire 5-mile tunnel alignment
- Stacked configuration between 13th Street and Stockton Avenue Facilities
- Side-by-side running track configuration east of 13th Street and north/west of Taylor Street (along Stockton Avenue)



Emergency Egress/Ventilation Facilities



Site identified for exhibit purposes only. Final location TBD



Next Steps

- Advance design of Optimized Single-Bore concept including assessment of any potential environmental, right-of-way, and utility considerations
- Develop cost estimate, schedule, and risk register
- Prepare documents to submit for FTA's Expedited Project Delivery Pilot Program

Next Steps

- Next CWG meeting:
July (TBD), 4:00 PM, Virtual Meeting
 - CWG Member Report Backs
 - Diridon Integrated Station
Concept Plan
 - Phase II Update
 - Construction Education &
Outreach Plan
 - Related Transportation
Planning Efforts
- Action Items